






PLAN AT BASE SLAB AND LADDER PLATFORM

Scale: 1/50

(ALL BEAMS ARE W8X31 (TYP) (UNO)







(ALL HORIZONTAL BRACES ARE WT3X10 (-75 MM) (TYP) (UNO)



PLAN AT TOS EL.96.734

Scale: 1/50

(ALL BEAMS ARE W6X20 (TYP) (UNO)



DETAIL OF SLIDE PLATE

SCALE 1:20

DETAIL OF RUNG


SCALE 1:20

CONNECTION DESIGN END FORCE SUMMARY							
SECTION	MEMBER	END FORCES (ULTIMATE)		SHEAR (kN)	V _y	MOMENT (kN-M)	
		AXIAL (kN)	COMPRESSION			M _x	M _y
BEAM	W12X35	10	10	10	105	-	-
	W10X35	10	10	10	80	-	-
	W8X31	10	10	10	30	-	-
	W6X20	10	10	10	15	-	-
VERTICAL BRACING	WT3X10	-	15	-	-	-	-
HORIZONTAL BRACING	WT3X10	15	15	-	-	-	-

NOTES:

- ALL FORCES & MOMENTS ARE FACTORED & REVERSIBLE (+/-).
- TRANSFER FORCES AT JUNCTIONS TO BE CONSIDERED FOR ALL POSSIBLE COMBINATIONS OF FORCES FROM ALL HORIZONTAL & VERTICAL MEMBERS CONNECTING TO THE JUNCTIONS.
- ALL CONNECTIONS TO BE DESIGNED FOR MEMBER FORCES MENTIONED IN THE TABLE ABOVE OR THE FORCES DESCRIBED BELOW. A, B & D WHICHEVER IS MOST CRITICAL.
 - ALL BRACE END CONNECTIONS TO BE DESIGNED FOR APL LOAD 30% OF THE MEMBER TENSION CAPACITY AS PER MAVEN STANDARD MD-101-SMEM-E-G-RT-CR1-0001.
 - ALL BEAM END SHEAR CONNECTIONS TO BE DESIGNED FOR A VERTICAL SHEAR FORCE 1*, 40 KN OR 15% OF THE MEMBER SHEAR CAPACITY AS PER MAVEN STANDARD MD-101-SMEM-E-G-RT-CR1-0001.
 - MOMENT CONNECTIONS SHALL BE DESIGNED FOR 50% OF MEMBER PLASTIC MOMENT CAPACITY & 50% OF MEMBER SHEAR CAPACITY AS PER MAVEN STANDARD MD-101-SMEM-E-G-RT-CR1-0001.
 - SPLICE CONNECTION SHALL BE DESIGNED FOR 100% OF MEMBER PLASTIC MOMENT CAPACITY & 50% OF MEMBER SHEAR CAPACITY OR 50% OF MEMBER AXIAL TENSION CAPACITY + 50% OF MEMBER SHEAR CAPACITY. WHICHEVER IS MORE CRITICAL. SPLICE PLATE AREA AT FLANGE & WEB SHALL BE 15% MORE THAN THE PLAIN & WEB AREA. THE MEMBER RESPECTIVELY.

EQUIPEMENT TAG N°	NORTHING	EASTING
522-89MH-VSL-001	3046579.980	322602.650
522-89MH-VSL-002	3046537.555	322602.650
522-89MH-VSL-004	3046281.980	322602.650
522-89MH-VSL-005	3046622.405	322602.650
522-89MH-VSL-006	3046664.820	322602.650
522-89MH-VSL-007	3046707.245	322602.650



- GENERAL NOTES:
- 1) ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.
 - 2) ALL CO-ORDINATES ARE BASED ON UTM 38R COORDINATE SYSTEM.
 - 3) ALL CO-ORDINATES AND LEVELS ARE IN METER UNLESS OTHERWISE SPECIFIED.
 - 4) FOR GENERAL CONCRETE NOTES REFER DWG. No. MD-520-1000-EG-CV-STD-0001.
 - 5) PLANT ELEVATION EL. 100.000 = 7.00M M.S.L. (COMPANY REFERENCE TO MEAN SEA LEVEL).
 - 6) THE TYPE OF CEMENT MUST FOLLOW THE DEFINITION IN THE GEOTECHNICAL REPORT.
 - 7) FOR ANY CLASHES WITH U/G SERVICES, REVERT TO DESIGN OFFICE.
 - 8) FOR CONSTRUCTION REFER TO DWG No.MD-520-1000-EG-CV-STD-0004 (UNO).
 - 9)FOR ANCHOR BOLTS DETAILS REFER TO DWG No.MD-520-1000-EG-CV-STD-0005.
 - 10) FOR INSERT PLATES REFER DWG No.MD-520-1000-EG-CV-STD-0010& AND CAST-IN ITEM DETAILS REFER DWG No.MD-520-1000-EG-CV-STD-0010.
 - 11)FOR LADDER ARRANGEMENT & DETAILS MD-520-1000-EG-ST-STD-0014 & MD-520-1000-EG-ST-STD-0015
 - 12)CONTRACTOR SHALL CONTINUOUSLY DEWATER ANY GROUNDWATER DURING CONSTRUCTION OF PITS TO ENSURE THAT THE GROUND WATER TABLE IS ALWAYS BELOW THE FOUNDING LEVEL OF THE PIT. THIS CONTINUOUS DEWATERING SHALL BE DONE UNTIL THE CONSTRUCTION OF THE FOUNDATION AND SIDE WALLS OF THE PITS AND BACKFILLING ABOVE BASE SLAB PROJECTION IS DONE.
 - 13)AT SLIDING END THE ANCHOR NUT SHALL NOT BE SNUG TIGHT BUT MUST ALLOW FOR LATERAL MOVEMENT.
 - 14)GROSS SAFE BEARING CAPACITY 150kN/m² IS CONSIDERED AT BOTTOM OF FOUNDATION.
 - 15) LAP SHALL BE STAGGERED BY CONTRACTOR WHEREVER REQUIRED.
 - 16) CONSTRUCTION JOINT LOCATION SHALL BE PROVIDED AS PER THE SITE CONDITION.
 - 17) FOR STRUCTURAL GENERAL NOTES, REFER DWG. NO. MD-522-1000-EG-ST-STD-0001.
 - 18) ALL BEAM TO BEAM CONNECTION WILL BE STANDARD SHEAR CONNECTION UNO. FOR STRUCTURAL STANDARD BEAM CONNECTIONS DETAILS, REFER DWG NO.MD-520-1000-EG-ST-STD-0002.
 - 19) FGL NEEDS TO BE CONFIRMED WITH SITE PRIOR TO CONSTRUCTION.

LEGEND & ABBREVIATION :

P: PEDESTAL

CJ: CONSTRUCTION JOINT

HOLD LIST :

PLATE			
REMARK			
BEAM TO BEAM			
BEAM TO BEAM			
BEAM TO BEAM			
BEAM TO BEAM			

ISSUED FOR CONSTRUCTION